

PORT DOUGLAS LAND DEVELOPMENTS PTY LTD

GEOTECHNICAL INVESTIGATION

PROPOSED PUMP STATION STAGE 1A & 1B PORT DOUGLAS ESTATE CAPTAIN COOK HIGHWAY, CRAIGLIE

REPORT NUMBER: GT19-242-001R REV 1

AUGUST 2019

REVISION 1



ETS Geo Pty Ltd

ABN 16 121 817 794 PO Box 587 Redlynch QLD 4870 BSA 1057711

Telephone: 07 4047 8600 Facsimile: 07 4047 8699 Email: admin@etsgeo.com.au

© 2019 ETS GEO PTY LTD

This document is and shall remain the property of ETS Geo Pty Ltd. This document may only be used for the purposes for which it was commissioned and in accordance with the Terms of Engagement for the commission. Unauthorised use of this document in any form whatsoever is prohibited.

This document is prepared under the agreed Terms of Engagement with the Client and may not be used by any third party. Third parties should obtain independent advice and no responsibility or liability is accepted by ETS Geo Pty Ltd for the use of this document by a third party.

	Distribution of Copies				
Revision Electronic Paper Issued to					
1	1		Ernest Duval		

	Document Status						
Revision			Reason for	Approved for Issue			
No.	Author	Reviewer	Issue	Name	Signature	Date	RPEQ
							No
1	C. de Bok	L. Jones	Final	M. Ganza	M. Sanza	29/8/19	4449
					03		



TABLE OF CONTENTS

1.		1
2.	STANDARDS & GUIDELINES	2
3.	PROPOSED DEVELOPMENT	2
4.	FIELDWORK	2
5.	LABORATORY TESTING	2
6.	SITE CONDITIONS AND OBSERVATIONS	3
7.	ENGINEERING ASSESSMENT AND RECOMMENDATIONS	4
8.	SEASONAL INFLUENCES	14
9.	CONSTRUCTION INSPECTION	14
10.	LIMITATIONS	14
APPE	ENDIX A – SITE PLAN	
APPE	ENDIX B – BOREHOLE LOGS	
APPE	ENDIX C – LABORATORY TEST RESULTS	
APPE	ENDIX D – PHOTOS	
	ENDIX E - UNDERSTAND THE LIMITATIONS OF YOUR FECHNICAL REPORT	



1. INTRODUCTION

ETS Geo Pty Ltd (ETS) has conducted a geotechnical investigation for the proposed pump station and pavement at the Stage 1A & 1B Port Douglas Estate subdivision on the Captain Cook Highway in Craiglie.

The objective of the geotechnical investigation for the pump station as defined by the client is to provide:

- The nature and type of sub-surface material including depths to and thicknesses of fill material, natural soils, rock, etc;
- Excavation conditions and shoring requirements for the construction of the wet well;
- Standing water level;
- Foundation recommendations:
 - Site Classification;
 - Allowable bearing capacity and estimated settlement at 7m below the existing ground surface levels;
- Horizontal bearing capacity at 1 1.5m below the existing ground surface levels;
- Preliminary Acid Sulfate Soil assessment; and
- Soaked CBR test at a depth between 0.2 1.0m below the existing ground surface level (pump station site).

The objective of the geotechnical investigation for the pavement design as defined by the client is to provide:

 Soaked CBR and Atterberg Limits test results for three (3) test pit locations nominated by the customer across the proposed subdivision area at a depth of 1 – 2m below the existing surface levels.



2. STANDARDS & GUIDELINES

The soil classification descriptions, field and laboratory testing were completed in general accordance with the following Australian Standards.

AS 1726-2017	Geotechnical Site Investigations
AS 1289	Methods of Testing Soils for Engineering Purposes

3. PROPOSED DEVELOPMENT

It is understood that a 7m deep 2.1m diameter manhole is proposed at the pump station, as well as associated structures to be founded on a 16m² concrete slab. The manhole has an approximate weight of 20t. A preliminary design was not available at this stage.

4. FIELDWORK

The fieldwork was conducted by ETS on the 15th of August 2019 and included a visual assessment of the site, its surrounds and a subsurface investigation. The fieldwork comprised:

- One (1) borehole was drilled to a depth of 9.0m with a truck mounted drill rig at the proposed pump station location with Standard Penetration Testing (SPT) and undisturbed U50 sampling at regular intervals, and
- Three (3) test pits to a depth of 2.5m in the vicinity of the proposed internal roads within the proposed subdivision with bulk sampling.

The test locations are presented on Drawing GT19-242-001 DWG in Appendix A. The results of the fieldwork (Borehole and test pit logs) are presented in Appendix B.

5. LABORATORY TESTING

The following laboratory testing was conducted in NATA accredited laboratories on samples recovered during fieldwork in order to assist with the assessment of geotechnical design parameters to be used in the analysis:



- Atterberg Limits;
- Particle Size Distribution;
- California Bearing Ratio (1pt STD);
- Soil pH_F and pH_{FOX} ; and
- Chromium Suite Analysis.

Results of the laboratory testing are presented in Appendix C.

6. SITE CONDITIONS AND OBSERVATIONS

6.1 Visual Assessment

The site is currently used for sugar cane farming and at the time of investigation the sugar cane had been harvested from the proposed subdivision site. The ground surfaces were generally described as being gently sloping to the East. An open drain of approximately 2m to 3m deep and 6m to 8m wide was present along the northern boundary. An open battered drain was also present on the western boundary between the cane field and the Bruce Highway and another shallow open drain was present to the East. A large stockpile of soil was present in the Northeastern corner of the site.

6.2 Subsurface Conditions

The 1:250,000 Geological Map of Mossman (1996) shows that the site is underlain by Quaternary deposits comprising "Mainly quartzose to lithic sublabile sand, muddy sand, silt, mud; rare peat: undivided coastal (supratidal, intertidal, beach-ridge, dune coastal-flat and swamp) deposits".

The subsurface conditions encountered are loose Clayey SAND underlain by very stiff to hard low plasticity CLAY with various contents of fine to medium grained sand. Table 1 presents a summary of the subsurface conditions.

Groundwater was encountered in BH1 at a depth of 2.2m during the fieldwork. It should be noted that groundwater levels are affected by climatic conditions and therefore groundwater levels may vary with time. The groundwater table was not encountered at the test pit locations which is likely attributed to higher ground surface levels at these locations.



Material Description	Depth Encountered (m)				
	BH1	TP1	TP2	TP3	
TOPSOIL: Sandy Silty CLAY (CL) Firm	0 – 0.3	-	-	-	
Clayey SAND (SC) Loose	0.3 – 1.1	-	-	-	
Sandy CLAY / Silty CLAY (CL) Very Stiff	1.1 – 7.0	0 – 0.3	0 – 0.35	0 – 0.3	
Silty CLAY (CL) Very Stiff to Hard	7.0 – 9.4	0.3 – 2.5	0.35 – 2.5	0.3 – 2.5	

TABLE 1: Subsurface Profile Summary

7. ENGINEERING ASSESSMENT AND RECOMMENDATIONS

7.1 Assessed Geotechnical Issues

Based on the available data the following geotechnical issues are considered to have some impact on the proposed pump station development at this site.

- Selection of a suitable footing system. The footing system chosen should be able to accommodate both compression loads (without excessive settlement) when the pump station is fully constructed and oppose uplift forces due to pore water pressure during and after construction;
- Excavation and support;
- Presence of Actual or Potential Acid Sulfate Soil.

The above potential geotechnical issues have been addressed in Sections 7.2, 7.4 and 7.5.

The potential presence of actual or potential acid sulfate soil across the subdivision at the pavement locations has also been identified and has also been discussed in Section 7.5.

Furthermore, the horizontal bearing capacity at 1m to 1.5m depth, geotechnical design parameters for the pavement design and earthworks recommendations are provided in Sections 7.3, 7.6 and &.7.7 respectively.



7.2 Suitable Foundation System

7.2.1 Pump Station Manhole

The base of the manhole is assumed to be located at 7m depth, below which very stiff to hard low to medium plasticity Silty CLAY was confirmed to be present to a depth of 9.4m.

Considering the depth and diameter of the manhole, an allowable bearing capacity of 300kPa may be adopted for the foundation of the manhole.

Considering the shallow groundwater table at the proposed pump station location and allowing for groundwater rising to within 0.5m of the ground surface around the pump station, the groundwater head associated with the floor construction at 7m depth equates with a uniform uplift pressure of approximately 65kPa. Based on discussions with Cardno, the deadweight from the pump station structure will be insufficient to counteract this uplift loading. Therefore measures should be taken to resist uplift of the manhole. Over excavation and backfill with concrete to increase the dead weight of the manhole or screw piles at the base of the excavation may be considered. Should the depth of the foundation (i.e. 7m) be altered, it is recommended the uplift pressure should similarly be reassessed.

7.2.2 Shallow Foundations

Shallow foundation conditions at the proposed pump station location comprise loose Clayey SAND up to 1.2m depth. Loose SAND is not considered suitable for shallow foundations and improvement of this sand layer, such as remove and re-compact in accordance with the earthworks recommendations provided in Section 7.7 may be considered. Alternatively, structures can be founded a minimum of 0.3m in the very stiff clay below the sand, i.e. at minimum 1.5m depth. It should be noted that the loose sand layer thickness may vary across the structure footprint.

An Allowable Bearing Capacity of 200kPa is readily achieved for footings (i.e. short bored piers) founded in the very stiff CLAY. The Allowable Bearing Capacity for foundations in the re-compacted sand depends on the dimensions of the foundation, as well as the achieved density of the sand after compaction. A medium dense sand can generally be achieved after appropriate compaction, in which an Allowable Bearing Capacity of 150kPa is readily achieved for a concrete slab of 3m by 5m. For



smaller footings, such as 0.3m wide strip footings, an Allowable Bearing Capacity of 100kPa is readily achieved. These assessments are based on the assumption that the groundwater table is not encountered within the zone of influence beneath the footing.

The anticipated immediate settlement below foundations of maximum 1m wide founded in the clay is less than 10mm, for a footing load of 100kPa. The anticipated immediate settlement below foundations of maximum 3m wide and 5m long founded in the sand is less than 10mm, for a footing load of 100kPa.

It is recommended that Dynamic Cone Penetrometer testing is undertaken in the excavated footings to confirm the required soil strength has been achieved and remains constant or improves to a depth equal to three (3) times the width of the footing.

All footings should be designed using engineering principles by an experienced and suitably qualified structural engineer.

7.2.3 Site Classification

It is noted that site classification in accordance with AS2870 may not be strictly applicable for the pump station structure. Assessment using engineering principals should be adopted. However, for completeness and any associated structures constructed at ground surface level within the near surrounds at the pump station location a site classification in accordance with AS2870 is provided.

Due to the soft soils encountered the site is classified as <u>**CLASS – P**</u> in accordance with AS2870-20111 "Residential Slabs and Footings – Construction".

Laboratory test results indicate that the soil is considered slightly reactive to changes in moisture content with an estimated characteristic surface movement (y_s) within the Class S category (0 to 20mm) in accordance with AS2870-2011² "Residential Slabs

¹ Australian Standard AS 2870-2011 "Residential Slabs and Footings – Construction", Standards Australia

² Australian Standard AS 2870-2011 "Residential Slabs and Footings – Construction", Standards Australia



and Footings – Construction". This classification is based on the site in its current state (i.e. no additional earthworks).

Should any filling be undertaken at the proposed structure location the estimated predicted ground surface movement (y_s) should be re-assessed as the reported site classification may change.

The characteristic surface movement (y_s) estimated in this report does not take into account the effects of future trees planted for landscaping purposes. It is recommended that any proposed landscaping for the project is reviewed by ETS well prior to construction phase to ensure that the given site classification for the site is not affected.

7.3 Horizontal Bearing Capacity

The Horizontal Bearing Capacity at 1m to 1.5m below surface level has been assessed, based on the ground conditions encountered at BH1. A loose Clayey SAND is present between depths of 1.0m and 1.2m and a very stiff low plasticity CLAY is present between depths of 1.2m and 1.5m depth. The Horizontal Bearing Capacity is considered equal to the horizontal passive pressure and is provided in Table 2.

	Horizontal Passive Pressure (Ultimate) (kPa)			
Depth	CLAY (CL) Very Stiff	Clayey SAND (SC) Loose		
1.0	-	24		
1.3	51	31		
1.5	57	36		

TABLE 2:	Horizontal Passive Pressure
----------	-----------------------------

1. The above calculations assume a water table level at 1.0m below the ground surface level.



7.4 Excavation Conditions and Support

It is anticipated that excavations will consist of the following:

- Small excavations- for foundations;
- Trenching for underground services and pipes; and
- Deep excavation for manhole.

Excavation through the loose SAND and very stiff CLAY for shallow foundations and trenches is expected to be readily undertaken using small earthmoving equipment (i.e. 5-10t excavator / small to medium size backhoe).

Excavation conditions for the manhole comprise loose sand to 1.2m underlain by very stiff low plasticity clay to 7m depth. Excavation through the very stiff CLAY for the manhole is expected to be undertaken using medium to large size earthmoving equipment (10t – 25t excavator).

Groundwater was encountered at 2.2m depth and therefore water seepage into the excavation is anticipated. Therefore a retention system, such as shoring or caisson sinking should be considered.

Lateral earth pressure coefficients for use in retention systems design are presented in Table 3. These recommended lateral earth pressure coefficients do not take into account a sloping backfill, surcharge loads or water pressures behind the excavation shoring. If the shoring is to be designed to resist water infiltration, then it would be advisable to also allow for some differential pressure between the outside and inside of the excavation, following dewatering of the excavation by pumping.

Material	Depth (m)	Unit Weight (kN/m³)	Friction Angle (º) (drained)		al Earth Coefficients K _p
Clayey SAND (SC) Loose	0.3 – 1.2	18	30	0.33	3.00
Sandy / Silty CLAY (CL) Very Stiff	1.2 – 7.0	19	28	0.36	2.77

TABLE 3: L	ateral Earth	Pressure	Coefficients
------------	--------------	----------	--------------



7.5 Preliminary Acid Sulfate Soil Assessment

The Douglas Shire's planning scheme operates under the repealed "State Planning Policy 02/02 (SPP 02/02); Planning and Managing Development Involving Acid Sulfate Soils" which requires consideration for Acid Sulfate Soils (ASS).

The site of the proposed development has the possibility of containing ASS, as they predominantly occur on coastal lowlands with elevations generally below 5m Australian Height Datum (AHD). Where excavations are likely to disturb \geq 100m³ of soil and are below 5m AHD, the investigation procedures outlined in the SPP 02/02 applies.

A preliminary ASS assessment was undertaken for the project which consisted of selecting eighteen (18) samples for pH_{FIELD} and pH_{FOX} screening tests. Following this testing and a review of the test results was completed, the following comments are provided in reference to the testing results:

- Where the soils pH (pH_{FIELD}) is less than 4, it is an indicator that actual acid sulfate soil (AASS) is present. None of the samples tested had a pH_{FIELD} value of less than 4.
- Where the pH after oxidation (pH_{FOX}) is less than 3, there is an effervescent reaction and the pH_{FOX} is lower than pH_F, it is an indicator that potential acid sulfate soil (PASS) is present. None of the samples fell into this category.
- If the pH_{FOX} is greater than 3 and less than 4 but still has an effervescent reaction and the pH_{FOX} is lower than pH_{FIELD} then the screening tests, it is an indicator that the material is possibly PASS and further quantative analysis is recommended. None of the samples fell into this category.

Following the preliminary screening tests, five (5) samples were selected for further quantative analysis in the form of Chromium Suite testing, which determines whether or not the specified action criterion are exceeded. The testing results are summarised below in Table 4, and the SGS Environmental test reports are included in Appendix C.



Test No.	Sample Depth (m)	Soil Description (Texture)	SCR (mol H⁺/t)	TAA (mol H⁺/t)
BH1	4.4 – 4.5	Fine	<5	<5
BH1	9.0 - 9.4	Fine	<5	<5
TP1	0.6 – 0.8	Fine	<5	15
TP2	0.35 – 0.55	Fine	<5	17
TP3	1.5 – 1.7	Fine	<5	7

Two (2) soil types (fine and medium texture) were identified during the investigation, however, only fine textured samples were selected for quantitative laboratory testing. The soil types correlating action criteria are specified in Appendix 5, Table 6 of the "State Planning Policy 2/02 Guideline". The criteria are used to define when ASS disturbed at a site will need to be treated and managed. The action criteria use the sum of the existing plus potential acidity (e.g. s-TAA + S_{CR} ; both expressed as moles H⁺/tonne & % w/w of S units) to set a trigger level for different soil texture types and amounts of material disturbed.

Considering the soil type (fine and coarse texture) and the quantity of soils likely to be disturbed, the action criteria in Table 5 apply.

Type of Material	Action Criteria if 1- 1000 tonnes of material is disturbed Existing + Potential Acidity			
Texture Range	Equivalent Sulfur (% w/w S)Equivalent acidity (mol H+)(oven-dry basis)tonne) (oven-dry basis)			
Medium	0.06	36		
Fine	0.1	62		

TABLE 5: Action Criteria A	SS
----------------------------	----



The threshold values for TAA and S_{CR} were not exceeded on any of the samples tested according to the soils texture type.

Based on the results of the preliminary ASS assessment, an Acid Sulfate Soil Management Plan is **not required** for the excavations and filling associated with this project.

7.6 Pavement Design Parameters

It is understood that pavement may be constructed at the site. Following earthworks, it is envisaged that a Sandy or Silty CLAY (CL) or Clayey Sand (SC) subgrade will be exposed. Laboratory testing has been carried out on the expected subgrade material from all test locations to determine this material's California Bearing Ratio (CBR), as well as its Atterberg Limits and Particle Size Distribution. The CBR value represents the 'strength' of this material, compacted to 98% standard compaction, under saturation. It is noted that the test locations and depths were nominated by the customers civil design engineers for the project.

The Soaked CBR test and Atterberg Limits test results are presented in Table 6.

	Depth Encountered (m)								
Test Type	BH1 0.2 – 0.4m	TP1 1.5 – 1.7m	TP2 1.3 – 1.5m	TP3 1.5 – 1.7m					
Liquid Limit (%)	-*	32	32	26					
Plastic Limit (%)	-	19	17	18					
Plastic Index	-	13	15	8					
Linear shrinkage (%)	-	8.0	7.5	5.5					
CBR Value (%)	15	11	15	11					

TABLE 6: Laboratory Test Results For Pavement Design

Notes: * Liquid Limit not obtainable due to fine grained sand content




7.7 Earthworks

The following general procedures are suggested for any site preparation and earthworks to be performed at the site:

- Strip & remove topsoil, soil containing significant amounts of organic materials, 'uncontrolled' fill and any deleterious soft, wet or highly compressible materials if encountered at subgrade or pavement formation levels;
- Undertake 'proof' rolling of the exposed surface levels across the site with a minimum 12 tonne static weight smooth drum roller or similar. Any soft or loose material that cannot be improved by compaction should be removed and replaced with approved select fill;
- Any exposed natural foundation soils should be compacted to a minimum dry density ratio of 98% using Standard compaction and moisture treated to a moisture range of -2%(dry) to +2%(wet) of optimum moisture content (OMC);
- Any exposed clay subgrade soils, at or close to formation level, should be sealed or covered as soon as practicable, in order to reduce the opportunity for desiccation and cracking (due to drying), or softening and swelling (due to wetting) with moist conditions;
- Where the formation levels are to be raised or subgrade materials are to be excavated (i.e. remove & replace), the foundation soils should be prepared as detailed above;
- Approved filling should be undertaken by placing fill in uniform horizontal layers not exceeding 200mm loose thickness and compact to achieve a dry density ratio of at least 98% using Standard compaction for cohesive soil or to at least 70% density index for sand. The moisture content of any cohesive soil fill materials should be maintained at -2% to +2% of OMC, during and after compaction;
- Filling should be placed at least two (2) metres beyond the design profile and then trimmed to the design profile.
- Where unsuitable materials are to be excavated it is recommended that all excavated in-situ soils are removed from the site and approved select fill is placed and compacted in the excavation. The excavation should be benched to "key in" the select fill material and optimise compaction. The benches



should slope back at 1V:5H and be at least 0.5m wide, refer to Figure 1a below.



- Approved filling (general fill) should be a well graded material free from organic materials, have a Plasticity Index less than or equal to 15%, and should not contain any individual particles greater than 75mm in size.
- In order for filling to be considered 'controlled' any earthworks that are undertaken beneath any of the proposed structures or pavements are to be performed under full time 'Level 1' inspection and testing as described and in accordance with AS3798:2007.

The above procedures will necessitate geotechnical inspection and testing services to be employed throughout construction.

It should be noted that there may be trafficability issues for rubber wheeled earthmoving equipment if construction activities are undertaken either during, or soon after, wet weather, due to the moistening and softening of the soils. In order to minimise these issues, the use of tracked equipment is suggested. In addition to this, achieving a satisfactory 'proof' roll under wet weather conditions may also be difficult. Should this situation arise, additional geotechnical advice should be sought.



8. SEASONAL INFLUENCES

Seasonal influences, i.e. "wet season" versus "dry season" may affect the foundation conditions on a site. At some sites softening of the cohesive soils (silt and clay) may be observed due to a higher moisture content in the soil compared to the moisture content at the time of the investigation. As a consequence, the undrained shear strength of the soil may be higher during the dry season and lower during the wet season. Therefore, if moisture conditions encountered during construction are considered to be different to those that were encountered during the fieldwork, it is recommended that additional geotechnical advice be sought. Depending on the circumstances, it may be necessary to modify the design or implement some form of foundation improvement.

9. CONSTRUCTION INSPECTION

Inspections by ETS Geo Pty Ltd shall be required for foundation excavations to confirm adequate conditions.

10. LIMITATIONS

We have prepared this report for the use of **PORT DOUGLAS LAND DEVELOPMENTS PTY LTD** for design purposes in accordance with generally accepted geotechnical engineering practices.

No other warranty, expressed or implied, is made as to the professional advice included in this report. This report has not been prepared for use by parties other than **PORT DOUGLAS LAND DEVELOPMENTS PTY LTD** or their design consultants, i.e. Architect & Civil/Structural Engineers. It may not contain sufficient information for purposes of other parties or for other uses. Your attention is drawn to the document - "Understand the Limitations of Your Geotechnical Report", which is included in Appendix C of this report. This document has been prepared to advise you of what your realistic expectations of this report should be, and to present you with recommendations on how to minimise the risks associated with the ground works for this project. The document is not intended to reduce the level of responsibility accepted by ETS, but rather to ensure that all parties who may rely on this report are aware of the responsibilities each assumes in so doing.



APPENDIX A – SITE PLAN



1	



APPENDIX B – BOREHOLE LOGS



		OLE					-	1 OF			GEC	DTECHNICA
		MER:					•	GT19-				
					& 1B	Port D		13/8/1	9			
				DK DB 2000				CDB				
		IODE					RL: COORDINATES:	- -	7125	000	N: 8170624.000 (55 I	
				. 100 11111			COORDINATES:	L. 337	133		11.0170024.000 (001	
DEPTH (m)	TECHNIQUE	SUPPORT	WATER	SAMPLE OR FIELD TEST	USCS SYMBOL	GRAPHIC LOG	SOIL/ROCK MATERIAL DESCRIPTION		MOISTURE CONDITION	CONSISTENCY DENSITY	STRUCTURE ANI ADDITIONAL OBSERVATIONS	
0					CL		TOPSOIL: Sandy Silty CLAY: low plasticity, grey-brown.			F		1 2
-				BS 0.20 - 0.40 m	SC		Clayey SAND: fine grained, pale yellow-brown, low plasti	icity.			-	-
- - 1 -				SPT 0.60 - 1.05 m 4, 2, 2 N=4	sc		Clayey SAND: fine to medium grained, pale grey, low pla	asticity.		L	0.6 - 0.8m Bulk sample	
-					_		Sandy CLAY: low plasticity, pale grey mottled yellow, fine medium grained.	e to			-	-
-				D 1.40 - 1.50 m U50 1.50 - 1.95 m	1		,				PP = 350, 420, 400kPa	-
- 2 -					CL				м		i = 550, 420, 400KFa	
-			22									-
-			13/08/19 10:551				Silty CLAY: low plasticity, pale orange-brown mottled gre fine to medium grained sand.	ey, with				
-			13/05	D 2 00 - 2 00			tine to medium grained sand.					-
3 -				D 2.90 - 3.00 m U50 3.00 - 3.45 m								
-					CL						PP = 300, 320, 320kPa	-
-												
4 -	AD/T	z					Sandy Silty CLAY: low plasticity, pale grey mottled			VSt		
-	-						yellow-brown, fine to medium grained.			VOL		
-				D 4.40 - 4.50 m U50 4.50 - 4.95 m								
- 5											PP = 300, 280, 250kPa	
-												
-					CL				M to W			
_												
3 -				D 5.90 - 6.00 m U50 6.00 - 6.45 m	7							
-											PP = 350, 320, 320kPa	
-												-
7 -				SPT 7.00 - 7.45 m		777	Silty CLAV: medium placticity, pole grou mettled servers	brown			-	
-				9, 15, 19 N=34			Silty CLAY: medium plasticity, pale grey mottled orange- trace of fine to medium grained sand.	JUOWII,				-
-					СІ				м	VSt to H		
-												-
	AS AD RR CB SUP I	auge roller	r scr r dril /trico or b	rewing N Iling U50 one D Iade bit BS PP HV	SPT undi distu bulk pocl (UC	- isturbe urbed s sampl	etrometer St stiff VSt very stiff H hard <i>Coarse</i> VL very loose	D M W	dr m	y oist et	CONDITION PEN 0 4	NETRATION no resistance to absolute refu
,	W	wate	r	$\overset{\blacktriangleright}{\neg}$	inflov partia	ling wa v al loss plete lo:	ter level L loose MD medium dense D dense SS VD very dense					

AS auger screwing AD auger drilling RR roller/tricone

CB claw or blade bit

SUPPORT C

- casing W water
- Ν none
- \cong standing water level

- → inflow
 → partial loss
 → complete loss

CONSISTENCY/DENSITY

- Fines VS very soft S soft
- S F St
- firm
- stiff
- VSt very stiff
- H hard Coarse

- VL very loose L loose MD medium dense D dense
- VD very dense

MOISTURE CONDITION D M dry moist

- 0
- no resistance

- to



5 MGA94)

но	LE D	IAM		t: 100 mm		1	COORDINATES: E:	337 135	.000,	N: 8170624.000 (55 MGA94)	
DEPTH (m)	TECHNIQUE	SUPPORT	WATER	SAMPLE OR FIELD TEST	USCS SYMBOL	GRAPHIC LOG	SOIL/ROCK MATERIAL DESCRIPTION	MOISTURE CONDITION	CONSISTENCY DENSITY	STRUCTURE AND ADDITIONAL OBSERVATIONS	PENETRATION
-8				SPT 8.00 - 8.45 m 8, 10, 15 N=25			Silty CLAY: medium plasticity, pale grey mottled orange-brow trace of fine to medium grained sand.	wn,			12
-	AD/T	z							VSt to		-
9 -					CI			M	H		
-	SPT	z		SPT 9.00 - 9.40 m 8, 16, 25/100mm Refusal N>50							-
-							BOREHOLE BH1 TERMINATED AT 9.40 m				
10 -										-	
-											
- 11 -											
-											
-											
12 -										-	
-											
- 13 -											
-											
14 -										-	
-											
- 15 -											
-											
-											
16											
		HNIQ		ewing N	NPLE SP ⁻		TESTING CONSISTENCY/DENSITY Fines	MOIST D dr		CONDITION PENETRAT 0 no resi	
Í	AD RR	auge rollei	er dril /trico	lling U50 one D	und (dist	listurbe urbed ទ	d tube dia mm VS very soft sample S soft		oist	to	te refus
(СВ	ciaw	or di	PP	poc (UC	S) kPa	netrometer St stiff VSt very stiff	NOTE	S		
		POR			han TER	id vane	H hard <i>Coarse</i> VL very loose				
١	W	casir wate none	r	∑ ►	stand	N	ter level L loose MD medium dense				
				_⊲	partia	al loss olete lo	D dense SS VD very dense				

TECHNIQUE

AS auger screwing AD auger drilling RR roller/tricone

CB claw or blade bit

SUPPORT

- casing C W
 - water

none

BS bulk sample PP pocket penetrometer (UCS) kPa

- HV hand vane

WATER

- \cong standing water level
- → inflow
 → partial loss
 → complete loss

CONSISTENCY/DENSITY

- Fines
- VS very soft S soft
- firm
- S F St stiff
- VSt very stiff
- H hard
- Coarse

- VL very loose L loose MD medium dense D dense
- VD very dense

MOISTURE CONDITION D M dry moist

- PENETRATION 0
 - no resistance to absolute refusal
 - 4

- NOTES



но	LE N	0.:	TP1				SHEET :	1 OF				GEOTECHNICA
		IER:				nd Developments	JOB NO :	GT19				
	OJEC			e 1A 8	& 1B P	ort Douglas Estate	DATE:	13/8/	19			
		D BY					REVIEWED BY:	CDB				
			Bobca	at			RL:	-	7000	000	NI- 0470	
PIT	DIM	ENSI	ONS: -				COORDINATES:	E: 33	/093	.000,	N: 8170	576.000 (55 MGA94)
DEPTH (m)	METHOD	WATER	SAMPLE OR FIELD TEST	USCS SYMBOL	GRAPHIC LOG	SOIL/ROCK MA	TERIAL DESCRIPTION		MOISTURE CONDITION	CONSISTENCY DENSITY	DCP (blows per 300mm)	STRUCTURE AND ADDITIONAL OBSERVATIONS
0.0-			D 0.10 - 0.30 m	CL		Silty CLAY: low plasticity, pale	grey-brown, trace of fine graine	ed sand.	D to N	VSt		
-						Silty CLAY: low plasticity, pale medium grained sand.	yellow mottled orange, trace of	fine to				
0.5 -			BS 0.60 - 0.80 m	_								
-				CL						VSt to H		
1.0 - -		ountered										
-	BU	Not Encountered				Silty CLAY: low plasticity, pale medium grained sand.	orange mottled yellow, with fine	e to	м			
1.5 - -			BS 1.50 - 1.70 m	-								
-				CL						н		
2.0 -												
-												
- 2.5						TEST TP1 TERMINATED AT 2.	50 m					
-												
- 3.0 -												
-												
- 3.5 - -												
-												
- 1.0												
	BU	H OD buck auge		U50 D	undis) distur bulk s	turbed tube dia mm Fi		Υ Μ D M W	dr m	y oist	CONDIT	ION PENETRATION 0 no resistance to 4 absolute refus
					(UCS hand) kPa S vane V H	t stiff St very stiff hard	Ν	IOTE	S		
				∑ ►	inflow	ng water level L M	oarse L very loose loose D medium dense dense					
					partial comple		D very dense					

WATER

- ✓ standing water level
 → inflow
 → partial loss
 → complete loss



			TF			nd Developments	SHEET :	1 OF GT19				GEOTECHNICA
	OJEC	MER: CT:			-	ort Douglas Estate	JOB NO : DATE:	13/8/				
		D BY:		-		0	REVIEWED BY:	CDB				
	CHIN			bcat			RL:	-				
PIT	DIM	ENSI	ONS: -			1	COORDINATES:	E: 336	6967 	.000,	N: 817046	60.000 (55 MGA94)
DEPTH (m)	METHOD	WATER	Sample of Field tes		GRAPHIC LOG	SOIL/ROCK I	VATERIAL DESCRIPTION		MOISTURE CONDITION	CONSISTENCY DENSITY	DCP (blows per 300mm)	STRUCTURE AND ADDITIONAL OBSERVATIONS
0.0-						Silty CLAY: low plasticity, pa	le grey.					
_				с		-			D to N	VSt		
-		-	BS 0.35 - 0.55 r	n		Silty CLAY: low plasticity, pa fine to medium grained sand.	le yellow mottled pale orange, tra	ace of				
0.5 -			BC 0 00 0 00 -							VSt to		
-			BS 0.60 - 0.80 r							н		
-												
- 1.0 -		_				Silty CLAY: low plasticity, pa medium grained sand.	le orange mottled pale yellow, wi	th fine to	1			
-		Not Encountered										
-	BU	t Enco										
-		No	BS 1.30 - 1.50 r	n								
1.5 -		-							M			
-												
				С						н		
_												
2.0 -						-						
-												
-												
2.5-						TEST TP2 TERMINATED AT	2.50 m					
-												
-												
-												
3.0 -												
-												
-												
- 3.5 -												
-												
-												
4.0												
I	ΒU	H OD bucke auge		U: D BS	50 undis distu 6 bulk	sturbed tube dia mm rbed sample sample	CONSISTENCY/DENSIT Fines VS very soft S soft	ry M D M W	dr m	y oist	CONDITIC	DN PENETRATION 0 no resistance to 4 absolute refus
				PF	pock /UCS		F firm St stiff		IOT-			
				Η	/ hand	vane	VSt very stiff	N	IOTE	S		
					ATER standi		H hard <i>Coarse</i> VL very loose L loose					
					inflow		MD medium dense D dense					
				\neg	partial		VD very dense	1				



	LE N		TP3				SHEET :	1 OF				GEOTECHNICA
		MER:				d Developments	JOB NO :	GT19				
			-	e 1A	& IBP	ort Douglas Estate		13/8/1	Э			
	GE		: DK Bobo	ot			REVIEWED BY:	CDB				
			ONS: -	αι			RL: COORDINATES:		7005	000	N· 8170	565.000 (55 MGA94)
FII							COORDINATES.	L. 001		.000,		(35 MGA34)
DEPTH (m)	METHOD	WATER	SAMPLE OR FIELD TEST	USCS SYMBOL	GRAPHIC LOG	SOIL/ROCK MA	ATERIAL DESCRIPTION		MOISTURE CONDITION	CONSISTENCY DENSITY	DCP (blows per 300mm)	STRUCTURE AND ADDITIONAL OBSERVATIONS
0.0-				_		Silty CLAY: low plasticity, pale	grey-brown.					
_			BS 0.10 - 0.30 m	CL					D to N	VSt		
-						Silty CLAY: low plasticity pale	vellow mottled pale orange tra	ce of				
-						Silty CLAY: low plasticity, pale fine to medium grained sand.	yonow motion paio orango, an	00 01				
0.5 -												
-			BS 0.60 - 0.80 m	CL						VSt to H		
-				\neg								
- 1.0 -		-										
		Not Encountered		-		Silty CLAY: low plasticity, pale	orange mottled pale vellow with	h fine to		L		
-	BU	Encot				medium grained sand.	erange motiled pale yellow, Wil					
	-	Not							м			
1.5 -			BS 1.50 - 1.70 m	_								
-			DO 1.00 1.70 m									
				CL						н		
-												
2.0 -												
-												
-												
2.5-						TEST TP3 TERMINATED AT 2	.50 m					
-												
-												
- 3.0 -												
-												
-												
]												
- 3.5 -												
-												
-												
4.0												
I	ΒU	HOD buck auge	et	U50 D	undis) distur	turbed tube dia mm <i>F</i> bed sample V	CONSISTENCY/DENSIT	D M	dr m	y oist	CONDIT	0 no resistance to
				PP BS	pocke	ample S et penetrometer F	firm	W	W	əl		4 absolute refus
					(UCS hand) kPa S vane V	it stiff ′St very stiff	N	OTE	S		
						F						
					TER	V	L very loose					
				►	inflow	-	ID medium dense					
				\neg	partial	loss D ete loss V) dense ′D very dense					
				-	comple		, -					




APPENDIX C – LABORATORY TEST RESULTS





Quality of Materials Report							
Client:	Port Douglas Land Developments Pty Ltd	Report Number:	GT19-242- CS31117 Q				
Client Address:	PO Box 13-413 Christchurch 8141 NZ.						
Job Number:	GT19-242	Report Date:	26/08/2019				
Project:	Proposed Sump Station, Wabul Street	Test Request No:	-				
Location	Craiglie						
Lab No:	CS31117		Sample Location:				
Date Sampled:	13/08/2019		BH 1				
Date Tested:	16/08/2019		55K 0337135				
Sampled By:	DK		8170624				
Sample Method:	AS1289.1.2.1.6.5.3		0.2 - 0.4m				
Material Source:	Insitu Material	Spec Description: -					
For Use As:	-	Lot Number: -					
Remarks:	-	Spec Number: -					



Plasticity Tests Air Dried - Dry Sieved	Test Method	Specification Minimum	Result	Specification Maximum
Liquid Limit (%)	AS1289.3.1.2	Slippage in Cup	o, Liquid Limit could n	ot be obtained.
Plastic Limit (%)	AS1289.3.2.1		*	
Plasticity Index	AS1289.3.3.1		*	
Linear Shrinkage (%)	AS1289.3.4.1		*	
P.I. X % Passing 0.425mm				
L.S. X % Passing 0.425mm				
Ratio of % Passing (0.075 / 0.425)			0.31	



Accredited for compliance with ISO/IEC 17025 - Testing

APPROVED SIGNATORY

FORM NUMBER

K. Kodpie


FM-RP-120-3

Karl Hodgson - Laboratory Manager NATA Accreditation No. 20026 Cairns Laboratory





Quality of Materials Report							
Client:	Port Douglas Land Developments Pty Ltd	Report Number:	GT19-242- CS31123 Q				
Client Address:	PO Box 13-413 Christchurch 8141 NZ.						
Job Number:	GT19-242	Report Date:	26/08/2019				
Project:	Proposed Sump Station, Wabul Street	Test Request No:	-				
Location	Craiglie						
Lab No:	CS31123		Sample Location:				
Date Sampled:	13/08/2019		BH 1				
Date Tested:	19/08/2019		55K 0337135				
Sampled By:	DK		8170624				
Sample Method:	AS1289.1.2.1.6.5.3		7.0 - 7.45				
Material Source:	Insitu Material	Spec Description: -					
For Use As:	-	Lot Number: -					
Remarks:	-	Spec Number: -					



Plasticity Tests Air Dried - Dry Sieved	Test Method	Specification Minimum	Result	Specification Maximum
Liquid Limit (%)	AS1289.3.1.2		42	
Plastic Limit (%)	AS1289.3.2.1		16	
Plasticity Index	AS1289.3.3.1		26	
Linear Shrinkage (%)	AS1289.3.4.1 *		13	
P.I. X % Passing 0.425mm			2565	
L.S. X % Passing 0.425mm			1282	
Ratio of % Passing (0.075 / 0.425)			0.95	

* 254mm linear shrinkage mould used, Shrinkage had cracked & curled.



Accredited for compliance with ISO/IEC 17025 - Testing

APPROVED SIGNATORY

K. Kodpe

Karl Hodgson - Laboratory Manager NATA Accreditation No. 20026 **Cairns Laboratory**

FM-RP-120-3

FORM NUMBER





	Atterberg Limits Report										
Client:	Port Douglas Land Developments Pty Ltd	Report Number:	GT19-242- CS31110 ATT								
Client Address:	PO Box 13-413 Christchurch 8141 NZ.										
Job Number:	GT19-242	Report Date:	26/08/2019								
Project:	Proposed Sump Station, Wabul Street	Order Number:	-								
Location	Craiglie										
Lab No:	CS31110	Sa	mple Location:								
Date Sampled:	13/08/2019		Test Pit 1								
Date Tested:	21/08/2019	5	5K 0337093								
Sampled By:	DK		8170576								
Sample Method:	A\$1289.1.2.1.6.5.4		1.5 - 1.7m								
Material Source:	Insitu Material	Lot Number:	-								
For Use As:		Sample History:	Air Dried								
Remarks:	-	Sample Preperation:	Dry Sieved								

Page 1 of 1

Plasticity Tests	Test Method	Specification	Result	Specification
		Minimum		Maximum
Liquid Limit (%)	AS1289 3.1.2	-	32	-
Plastic Limit (%)	AS1289 3.2.1	-	19	-
Plasticity Index	AS1289 3.3.1	-	13	-
Linear Shrinkage (%)	AS1289.3.4.1 *	-	8.0	-

* 250mm linear shrinkage mould used, Shrinkage had cracked.

		APPROVED SIGNATORY	FORM NUMBER
NATA	Accredited for compliance with ISO/IEC 17025 - Testing.	K. Kodpre	FM-RP-125 2
ACCREDITED FOR TECHNICAL		Karl Hodgson - Laboratory Manager	
COMPETENCE		Cairns Laboratory	
		NATA Accreditation No. 20026	






	Atterberg Limits Report										
Client:	Port Douglas Land Developments Pty Ltd	Report Number:	GT19-242- CS31113 ATT								
Client Address:	PO Box 13-413 Christchurch 8141 NZ.										
Job Number:	GT19-242	Report Date:	26/08/2019								
Project:	Proposed Sump Station, Wabul Street	Order Number:	-								
Location	Craiglie										
Lab No:	CS31113	Sa	mple Location:								
Date Sampled:	13/08/2019		Test Pit 2								
Date Tested:	21/08/2019	5	5K 0336967								
Sampled By:	DK		8170460								
Sample Method:	AS1289.1.2.1.6.5.4		1.3 - 1.5m								
Material Source:	Insitu Material	Lot Number:	-								
For Use As:	-	Sample History:	Air Dried								
Remarks:	-	Sample Preperation:	Dry Sieved								

Page 1 of 1

Plasticity Tests	Test Method	Specification	Result	Specification
		Minimum		Maximum
Liquid Limit (%)	AS1289 3.1.2	-	32	-
Plastic Limit (%)	AS1289 3.2.1	-	17	-
Plasticity Index	AS1289 3.3.1	-	15	-
Linear Shrinkage (%)	AS1289.3.4.1 *	-	7.5	-

* 250mm linear shrinkage mould used, Shrinkage had cracked.







Atterberg Limits Report										
Client:	Port Douglas Land Developments Pty Ltd	Report Number:	GT19-242- CS31116 ATT							
Client Address:	PO Box 13-413 Christchurch 8141 NZ.									
Job Number:	GT19-242	Report Date:	26/08/2019							
Project:	Proposed Sump Station, Wabul Street	Order Number:	-							
Location	Craiglie									
Lab No:	CS31116	Sa	mple Location:							
Date Sampled:	13/08/2019		Test Pit 3							
Date Tested:	21/08/2019	5	5K 0337135							
Sampled By:	DK		8170624							
Sample Method:	A\$1289.1.2.1.6.5.4		1.5 - 1.7m							
Material Source:	Insitu Material	Lot Number:	-							
For Use As:	-	Sample History:	Air Dried							
Remarks:	-	Sample Preperation:	Dry Sieved							

Page 1 of 1

Plasticity Tests	Test Method	Specification	Result	Specification
		Minimum		Maximum
Liquid Limit (%)	AS1289 3.1.2	-	26	-
Plastic Limit (%)	AS1289 3.2.1	-	18	-
Plasticity Index	AS1289 3.3.1	-	8	-
Linear Shrinkage (%)	AS1289.3.4.1 *	-	5.5	-

* 250mm linear shrinkage mould used, Shrinkage had not cracked, crumbled or curled.

		APPROVED SIGNATORY	FORM NUMBER
	Accredited for compliance with ISO/IEC 17025 - Testing.	K. Hodge	FM-RP-125 2
ACCREDITED FOR		Karl Hodgson - Laboratory Manager	
COMPETENCE		Cairns Laboratory	
		NATA Accreditation No. 20026	





Port Douglas Land Developments Pty Ltd Client: Report Number: GT19-242 -CS31117 CBR PO Box 13-413 Christchurch 8141 NZ. Client address: GT19-242 26/08/2019 Job Number: Report Date: **Proposed Sump Station, Wabul Street** Project: Order Number: Craiglie Location Lab No: CS31117 Sample Location 13/08/2019 Date Sampled: BH 1 Date Tested: 21/08/2019 55K 0337135 DK 8170624 Sampled By: Sample Method: AS1289.1.2.1.6.5.3 0.2 - 0.4m Insitu Material Material Source: Test Method : AS 1289.6.1.1 For Use As: Lot Number: -Remarks: Item Number Page 1 of 1 12.0 10.0 8.0 Load (kn) 6.0 4.0 2.0 0.0 0.5 5.5 . 2.0 2.5 3.0 3.5 4.0 . 5.0 7.0 9.0 9.5 10.0 10.5 11.0 11.5 12.0 12.5 13.0 0.0 1.0 4.5 6.0 6.5 7.5 8.0 8.5 1.5 Penetration (mm) Maximum Dry Density - MDD (t/m³) : 1.818 Dry Density after Soak (t/m³) : 1.783 Optimum Moisture Content - OMC (%) : 13.5 Moisture Content after Soak (%) 15.9 Compactive Effort : Standard Density Ratio after Soak (%) : 98 Nominated % Maximum Dry Density Compaction : 98 Hygroscopic Moisture Content (%) : 10.4 Nominated % Optimum Moisture Content 100.0 Moisture Content (Top) after Penetration (%) : 16.8 Compaction : Optional Moisture Content (Remainder) after Achieved Dry Density before Soak (t/m³) : 1.782 16.2 Penetration (%) : Achieved Percentage of Maximum Dry Density (%) : 98 CBR 2.5mm (%) : 15 13.5 9 Achieved Moisture Content (%) : CBR 5.0mm (%) : Achieved Percentage of Optimum Moisture Content 15 100 CBR Value (%) : (%): Test Condition (Soaked/Unsoaked) / Soaking Period Soaked / 4 Minimum Specified CBR Value (%) : -(Days) : Swell (%) / Surcharge (kg): Oversize Material (%) 0.0 / 4.5

California Bearing Ratio Report (1 Point)

Soil Description :

Refer Borehole Log.





Accredited for compliance with ISO/IEC 17025 - Testing.

Approved Signatory

Form Number

K. Hodpe

FM-RP-121-5

Karl Hodgson - Lab Manager **Cairns Laboratory**



Client:


Project:

Location Lab No:



26/08/2019

California Bearing Ratio Report (1 Point) GT19-242 -CS31110 CBR Port Douglas Land Developments Pty Ltd Report Number: PO Box 13-413 Christchurch 8141 NZ. Client address: GT19-242 Job Number: Report Date: **Proposed Sump Station, Wabul Street** Order Number: Craiglie CS31110 Sample Location 13/08/2019 Date Sampled: Test Pit 1 Date Tested: 21/08/2019 55K 0337093 DK 8170576 Sampled By: AS1289.1.2.1.6.5.4 1.5 - 1.7m Insitu Material Test Method : Lot Number: Item Number





Approved Signatory K. Hodge

Form Number

Karl Hodgson - Lab Manager **Cairns Laboratory**



ACCREDITED FOR TECHNICAL COMPETENCE



California Bearing Ratio Report (1 Point)

Client: Port Douglas Land Client address: PO Box 13-413 Ch														ł									Repo								(GT:	19-2	242 -CS31113 CBR									
Job Number: GT19-242 Project: Proposed Sump Si Location Craiglie						Sta	tion	, w	abu	ıl St	ree	t										Report Date: Order Number:										-	26,	/08/	2019								
Lab No: CS31113 Date Sampled: 13/08/2019 Date Tested: 21/08/2019 Sampled By: DK Sample Method: AS1289.1.2.1.6.5 Material Source: Insitu Material				.4																Sample Locatio Test Pit 2 55K 0336967 8170460 1.3 - 1.5m Test Method :								7	AS 12	289.	6.1.:	L											
or Use /					-																				ot N													-					
emarks					-																					I	tem	Nu	mbe	er :										-	Pa	ige 1	of 1
8.0	Π																																							_			
7.0																												7	/														
6.0	H																								/																		
																						$\left \right\rangle$	/																				
5.0	F																			/																							
(ku) 4.0																		/	1																			_		+		•	
Log															/	/																											
3.0	Ē												7					•	-			-																					
2.0											/	-	*																														
								×	_																															Ŧ			
1.0																																								F			
0.0		/																																						⋢			
	0.0	0	.5	1.	0	1.	5	2.0	:	2.5	3	8.0	3.5	4	.0	4.5	5	.0	5.5	6 F	.0 Penetr	6.5 atio		7.0 n)	7.5	8	.0	8.5	5	9.0	9.5	5	10.0) 1	10.5	11	1.0	11.	5 1	12.0	1	2.5	13.0
M	vin		201	Don	itu	N4	DD (t	/m ³								1 0	867					T			Dov)onci	tu off	or	Cook	(+/m ³	١.								1	02	1		
											-												Dry Density after Soak (t/m ³) :							1.831													
Opti	mui	m M	oist	ure	Cont	tent	- ON	1C (%):							14	4.2						Moisture Content after Soak (%) :																				
		Co	mp	activ	/e E	ffor	::								S	tan	Idar	d					Density Ratio after Soak (%) :														98						
Nominate											:					9	8						Hygroscopic Moisture Content (%) :												1	13.2	2						
Nomi	nat	ed %		timu mpa			ture	Con	tent							10	0.0						Mo	oistu	e Cor	itent	(Тор) af	ter Pe	enetr	atior	n (%)	:						1	18.3	3		
Achie	ved	Dry	Der	nsity	bef	ore	Soak	(t/ı	m³):							1.8	835					T	O	ption	al Mo		e Cor netra				der)	afte	r						1	16.4	L		
chieved	Perc	enta	ige (of M	axir	nun	n Dry	Der	nsity	(%)	:					9	98					T					R 2.5													15			
,	Achi	evec	l Mo	oistu	re C	Cont	ent (%):			\uparrow					13	3.9					\dagger				СВ	R 5.0	mm	(%) :	:				\square						14			
Achieved I	Perc	enta	ge o	of Op (%		um	Mois	tur	e Coi	nten	nt					9	98					\dagger				СВ	R Va	lue	(%)	:										15			
Test Cond	itior	n (So		d/Ui	isoa	aked) / Sc	baki	ng Pe	erio	d				Soal	ed	1	4				\dagger		М	inimu	ım Sp	pecifi	ed C	BR V	'alue	(%) :									-			
(Days) : Swell (%) / Surcharge (kg):						T						1					╈			Minimum Specified CBR Value (%) : Oversize Material (%)								_															
oil Desc	ript	tion	:		Rei	fer	Test	Pit	t Lo	g.																								1									
									-1	<u> </u>																Т				Арр	rov	04 G	Sig	12+0	n.				1	_	For	m N·	mbe
																														чþţ	VUn	eu S	ngi	iatO	чy				╞		ruf	III INU	mue
Ň/	1.	Ţ	A						Acc	red	litor	d for	cor	nnlia	ince	wit	h IS)/IF(^ 17	025	- 70	tin	σ							K	. 1	40	J	ne							FIV	- RP- :	121-5
Accre								201					J, IL	- 1/	525	103	-citi;	ο.																									

Karl Hodgson - Lab Manager Cairns Laboratory





California Bearing Ratio Report (1 Point) Port Douglas Land Developments Pty Ltd Client: Report Number: GT19-242 -CS31116 CBR PO Box 13-413 Christchurch 8141 NZ. Client address: GT19-242 26/08/2019 Job Number: Report Date: **Proposed Sump Station, Wabul Street** Project: Order Number: Craiglie Location Lab No: CS31116 Sample Location 13/08/2019 Date Sampled: Test Pit 3 Date Tested: 23/08/2019 55K 0337135 DK 8170624 Sampled By: Sample Method: AS1289.1.2.1.6.5.4 1.5 - 1.7m Insitu Material Material Source: Test Method : AS 1289.6.1.1 For Use As: Lot Number: -Remarks: Item Number Page 1 of 1 7.0 6.0 5.0 4.0 ŝ Load 3.0 2.0 1.0 0.0 0.0 0.5 2.0 3.5 9.0 10.0 10.5 11.0 11.5 12.0 12.5 13.0 1.0 2.5 3.0 4.0 4.5 5.0 5.5 6.0 6.5 7.0 7.5 8.0 8.5 9.5 1.5 Penetration (mm) Maximum Dry Density - MDD (t/m³) : 1.831 Dry Density after Soak (t/m³) : 1.783 11.7 Optimum Moisture Content - OMC (%) : Moisture Content after Soak (%) 18.4 Compactive Effort : Standard Density Ratio after Soak (%) : 97 Nominated % Maximum Dry Density Compaction : 98 Hygroscopic Moisture Content (%) : 12.1 Nominated % Optimum Moisture Content 100.0 Moisture Content (Top) after Penetration (%) : 15.7 Compaction : Optional Moisture Content (Remainder) after Achieved Dry Density before Soak (t/m³) : 1.792 16.5 Penetration (%) : Achieved Percentage of Maximum Dry Density (%) : 98 CBR 2.5mm (%) : 11 12.2 11 Achieved Moisture Content (%) : CBR 5.0mm (%) : Achieved Percentage of Optimum Moisture Content 104 11 CBR Value (%) : (%): Test Condition (Soaked/Unsoaked) / Soaking Period Soaked / 4 Minimum Specified CBR Value (%) : -(Days) : Swell (%) / Surcharge (kg): Oversize Material (%) % Excluded 0.0 / 4.5

Soil Description : Re

Refer Test Pit Log.



Accredited for compliance with ISO/IEC 17025 - Testing.

Approved Signatory

Form Number

K. Hodpie-

Karl Hodgson - Lab Manager Cairns Laboratory





ACID SULFATE SOILS FIELD TESTING REPORT

IFOX RESULLS
Report No: GT19-242-001 ASS
Order No:
Tested By: Darren Koch
Site or Lab: Cairns
Tested Date: 15 th August 2019

BOREHOLE NO: 1

Field Test No.	Description	Depth	pH F	pH FOX	Reaction*
1	Clayey SAND	0.2 - 0.4	6.64	6.01	XX
2	Clayey SAND	0.6 - 0.8	6.35	5.81	XX
3	Sandy CLAY	1.4 - 1.5	6.86	5.91	XX
4	Silty CLAY	2.9 - 3.0	6.78	5.35	XX
5	Sandy Silty CLAY	4.4 - 4.5	6.43	5.22	XX
6	Sandy Silty CLAY	5.9 - 6.0	6.68	6.01	XX
7	Silty CLAY	7.0 - 7.45	6.51	5.83	Х
8	Silty CLAY	8.0-8.45	6.71	5.99	Х
9	Silty CLAY	9.0 - 9.45	6.32	5.30	Х
10					

• Rate reaction with peroxide: X = low, XX = medium, XXX = high, XXXX = extreme

tdetab

SIGNATURE:

SIGNED BY: Cynthia de Bok POSITION: Geotechnicial Engineer DATED: 19th August 2019 ETS Laboratory: Cairns





ACID SULFATE SOILS FIELD TESTING REPORT

prif and pr	IFOX NESUIIS
Client: Port Douglas Land Developments Pty Ltd	Report No: GT19-242-002 ASS
Project: Stages 1A & 1B Port Douglas Estate	Order No:
Captain Cook Highway	
Craiglie QLD 4877	
Sampled By: Darren Koch	Tested By: Darren Koch
Sampled Date: 13 th August 2019	Site or Lab: Cairns
	Tested Date: 15 th August 2019

TEST PIT NO: 1

Field Test No.	Description	Depth	pH F	pH FOX	Reaction*
1	Silty CLAY	0.1 - 0.3	6.25	5.68	XXX
2	Silty CLAY	0.6 - 0.8	5.94	5.34	XX
3	Silty CLAY	1.5 - 1.7	5.92	5.61	XX
4					
5					
6					
7					
8					
9					
10					

• Rate reaction with peroxide: X = low, XX = medium, XXX = high, XXXX = extreme

tdetab

SIGNATURE:

SIGNED BY: Cynthia de Bok POSITION: Geotechnicial Engineer DATED: 19th August 2019 ETS Laboratory: Cairns





ACID SULFATE SOILS FIELD TESTING REPORT

prif and pr	IFOX NESUIIS
Client: Port Douglas Land Developments Pty Ltd	Report No: GT19-242-002 ASS
Project: Stages 1A & 1B Port Douglas Estate	Order No:
Captain Cook Highway	
Craiglie QLD 4877	
Sampled By: Darren Koch	Tested By: Darren Koch
Sampled Date: 13 th August 2019	Site or Lab: Cairns
	Tested Date: 15 th August 2019

TEST PIT NO: 2

Field Test No.	Description	Depth	pH F	pH FOX	Reaction*
1051 110.					
1	Silty CLAY	0.35 - 0.55	5.50	5.32	XX
2	Silty CLAY	0.6 - 0.8	6.11	5.83	XX
3	Silty CLAY	1.3 - 1.5	6.29	5.83	XX
4					
5					
6					
7					
8					
9					
10					

• Rate reaction with peroxide: X = low, XX = medium, XXX = high, XXXX = extreme

tdetab

SIGNATURE:

SIGNED BY: Cynthia de Bok POSITION: Geotechnicial Engineer DATED: 19th August 2019 ETS Laboratory: Cairns





ACID SULFATE SOILS FIELD TESTING REPORT

	IFOX INCOULTS
Client: Port Douglas Land Developments Pty Ltd	Report No: GT19-242-002 ASS
Project: Stages 1A & 1B Port Douglas Estate	Order No:
Captain Cook Highway	
Craiglie QLD 4877	
Sampled By: Darren Koch	Tested By: Darren Koch
Sampled Date: 13 th August 2019	Site or Lab: Cairns
	Tested Date: 15 th August 2019

TEST PIT NO: 3

Field Test No.	Description	Depth	pH F	pH FOX	Reaction *
1	Silty CLAY	0.1 - 0.3	5.81	5.31	XX
2	Silty CLAY	0.6 - 0.8	6.08	5.75	XX
3	Silty CLAY	1.5 - 1.7	5.81	5.21	XX
4					
5					
6					
7					
8					
9					
10					

• Rate reaction with peroxide: X = low, XX = medium, XXX = high, XXXX = extreme

tdetab

SIGNATURE:

SIGNED BY: Cynthia de Bok POSITION: Geotechnicial Engineer DATED: 19th August 2019 ETS Laboratory: Cairns



ANALYTICAL REPORT



- CLIENT DETAILS		LABORATORY DETAI	
Contact	Darren Koch	Manager	Anthony Nilsson
Client	ETS GEO PTY LTD	Laboratory	SGS Cairns Environmental
Address	PO BOX 587 REDLYNCH QLD 4870	Address	Unit 2, 58 Comport St Portsmith QLD 4870
Telephone	61 7 4047 8600	Telephone	+61 07 4035 5111
Facsimile	(Not specified)	Facsimile	+61 07 4035 5122
Email	darrenk@etsgeo.com.au	Email	AU.Environmental.Cairns@sgs.com
Project	GT19-242 Proposed Pump Stn Craiglie	SGS Reference	CE141386 R1
5			
Order Number	GEO-291	Date Received	16 Aug 2019
Samples	5	Date Reported	27 Aug 2019

COMMENTS _

Accredited for compliance with ISO/IEC 17025 - Testing. NATA accredited laboratory 2562(3146).

This report cancels and supersedes the report No.CE141386-R0. dated 23/08/19 issued by SGS Environment, Health and Safety due to amended sample ids.

SIGNATORIES _

Anthony Nilsson Operations Manager

Jon Dicker Manager Northern QLD

SGS Australia Pty Ltd ABN 44 000 964 278

Environment, Health and Safety

Unit 2 58 Comport St

St Portsmith QLD 4870

Australia t +61 7 4035 5111 f +61 7 4035 5122

www.sgs.com.au



ANALYTICAL REPORT

CE141386 R1

	Sa	nple Number ample Matrix Sample Date ample Name	Soil 13 Aug 2019	CE141386.002 Soil 13 Aug 2019 BH1 9.0-9.45m	CE141386.003 Soil 13 Aug 2019 TP1 0.6-0.8m	CE141386.004 Soil 13 Aug 2019 TP2 0.35-0.55m
Parameter	Units	LOR				
Moisture Content Method: AN002 Tested: 16/8/2019						
% Moisture	%w/w	0.5	16	15	13	12

TAA (Titratable Actual Acidity) Method: AN219 Tested: 23/8/2019

pH KCI	pH Units	-	5.6	5.5	5.1	4.8
Titratable Actual Acidity	kg H2SO4/T	0.25	<0.25	<0.25	0.74	0.86
Titratable Actual Acidity (TAA) moles H+/tonne	moles H+/T	5	<5	<5	15	17
Titratable Actual Acidity (TAA) S%w/w	%w/w S	0.01	<0.01	<0.01	0.02	0.03
Sulphur (SKCI)	%w/w	0.005	<0.005	<0.005	0.006	<0.005

Chromium Reducible Sulphur (CRS) Method: AN217 Tested: 23/8/2019

Chromium Reducible Sulphur (Scr)	%	0.005	<0.005	<0.005	<0.005	<0.005
Chromium Reducible Sulphur (Scr)	moles H+/T	5	<5	<5	<5	<5

Chromium Suite Net Acidity Calculations Method: AN220 Tested: 23/8/2019

s-Net Acidity	%w/w S	0.005	0.010	0.010	0.028	0.030
a-Net Acidity	moles H+/T	5	6	6	17	19
Liming Rate	kg CaCO3/T	0.1	NA	NA	NA	1.4
Verification s-Net Acidity	%w/w S	-20	0.00	0.00	0.00	0.00
a-Net Acidity without ANCBT	moles H+/T	5	6	6	17	19
Liming Rate without ANCBT	kg CaCO3/T	0.1	NA	NA	NA	1.4

HCI Extractable S, Ca and Mg in Soil ICP OES Method: AN014 Tested: 23/8/2019

Acid Soluble Sulfur (SHCI)	%w/w	0.005	<0.005	<0.005	0.011	0.010



ANALYTICAL REPORT

			Sample Number Sample Matrix Sample Date Sample Name		x Soil e 13 Aug 2019
Parameter			Units	LOR	
Moisture Content	Method: AN002	Tested: 16/8/2019			
% Moisture			%w/w	0.5	14

TAA (Titratable Actual Acidity) Method: AN219 Tested: 23/8/2019

рН КСІ	pH Units	-	5.5
Titratable Actual Acidity	kg H2SO4/T	0.25	0.37
Titratable Actual Acidity (TAA) moles H+/tonne	moles H+/T	5	7
Titratable Actual Acidity (TAA) S%w/w	%w/w S	0.01	0.01
Sulphur (SKCI)	%w/w	0.005	<0.005

Chromium Reducible Sulphur (CRS) Method: AN217 Tested: 23/8/2019

Chromium Reducible Sulphur (Scr)	%	0.005	<0.005
Chromium Reducible Sulphur (Scr)	moles H+/T	5	<5

Chromium Suite Net Acidity Calculations Method: AN220 Tested: 23/8/2019

s-Net Acidity	%w/w S	0.005	0.014
a-Net Acidity	moles H+/T	5	9
Liming Rate	kg CaCO3/T	0.1	NA
Verification s-Net Acidity	%w/w S	-20	0.00
a-Net Acidity without ANCBT	moles H+/T	5	9
Liming Rate without ANCBT	kg CaCO3/T	0.1	NA

HCI Extractable S, Ca and Mg in Soil ICP OES Method: AN014 Tested: 23/8/2019

Acid Soluble Sulfur (SHCI)	%w/w	0.005	<0.005



QC SUMMARY

MB blank results are compared to the Limit of Reporting LCS and MS spike recoveries are measured as the percentage of analyte recovered from the sample compared the the amount of analyte spiked into the sample. DUP and MSD relative percent differences are measured against their original counterpart samples according to the formula : *the absolute difference of the two results divided by the average of the two results as a percentage*. Where the DUP RPD is 'NA', the results are less than the LOR and thus the RPD is not applicable.

Chromium Reducible Sulphur (CRS) Method: ME-(AU)-[ENV]AN217

Parameter	QC Reference	Units	LOR	MB	DUP %RPD	LCS %Recovery
Chromium Reducible Sulphur (Scr)	LB070769	%	0.005	<0.005	0%	97%
Chromium Reducible Sulphur (Scr)	LB070769	moles H+/T	5	<5		

TAA (Titratable Actual Acidity) Method: ME-(AU)-[ENV]AN219

Parameter	QC Reference	Units	LOR	MB	DUP %RPD	LCS %Recovery
pH KCI	LB070766	pH Units	-	6.0	0%	101%
Titratable Actual Acidity	LB070766	kg H2SO4/T	0.25	<0.25	0%	NA
Titratable Actual Acidity (TAA) moles H+/tonne	LB070766	moles H+/T	5	<5	0%	92%
Titratable Actual Acidity (TAA) S%w/w	LB070766	%w/w S	0.01	<0.01	0%	92%



METHOD SUMMARY

METHOD	METHODOLOGY SUMMARY
AN002	The test is carried out by drying (at either 40°C or 105°C) a known mass of sample in a weighed evaporating basin. After fully dry the sample is re-weighed. Samples such as sludge and sediment having high percentages of moisture will take some time in a drying oven for complete removal of water.
AN014	This method is for the determination of soluble sulfate (SO4-S) by extraction with hydrochloric acid. Sulphides should not react and would normally be expelled. Sulfur is determined by ICP.
AN217	Dried pulped sample is mixed with acid and chromium metal in a rapid distillation unit to produce hydrogen sulfide (H2S) which is collected and titrated with iodine (I2(aq)) to measure SCR.
AN219	Dried pulped sample is extracted for 4 hours in a 1 M KCl solution. The ratio of sample to solution is 1:40. The extract is titrated for acidity. Calcium, magnesium, and sulfur are determined by ICP-AES.
AN220	Chromium Suite: Scheme for the calculation of net acidities and liming rates using a Fineness Factor of 1.5.



FOOTNOTES _

SGS

IS	Insufficient sample for analysis.
LNR	Sample listed, but not received.
*	NATA accreditation does not cover the

- performance of this service.
- ** Indicative data, theoretical holding time exceeded.
- LOR Limit of Reporting
- ↑↓ Raised or Lowered Limit of Reporting
- QFH QC result is above the upper tolerance
- QFL QC result is below the lower tolerance - The sample was not analysed for this analyte
- NVL Not Validated

Unless it is reported that sampling has been performed by SGS, the samples have been analysed as received. Solid samples expressed on a dry weight basis.

Where "Total" analyte groups are reported (for example, Total PAHs, Total OC Pesticides) the total will be calculated as the sum of the individual analytes, with those analytes that are reported as <LOR being assumed to be zero. The summed (Total) limit of reporting is calcuated by summing the individual analyte LORs and dividing by two. For example, where 16 individual analytes are being summed and each has an LOR of 0.1 mg/kg, the "Totals" LOR will be 1.6 / 2 (0.8 mg/kg). Where only 2 analytes are being summed, the "Total" LOR will be the sum of those two LORs.

Some totals may not appear to add up because the total is rounded after adding up the raw values.

If reported, measurement uncertainty follow the ± sign after the analytical result and is expressed as the expanded uncertainty calculated using a coverage factor of 2, providing a level of confidence of approximately 95%, unless stated otherwise in the comments section of this report.

Results reported for samples tested under test methods with codes starting with ARS-SOP, radionuclide or gross radioactivity concentrations are expressed in becquerel (Bq) per unit of mass or volume or per wipe as stated on the report. Becquerel is the SI unit for activity and equals one nuclear transformation per second.

Note that in terms of units of radioactivity:

- a. 1 Bq is equivalent to 27 pCi
- b. 37 MBq is equivalent to 1 mCi

For results reported for samples tested under test methods with codes starting with ARS-SOP, less than (<) values indicate the detection limit for each radionuclide or parameter for the measurement system used. The respective detection limits have been calculated in accordance with ISO 11929.

The QC and MU criteria are subject to internal review according to the SGS QAQC plan and may be provided on request or alternatively can be found here: <u>www.sgs.com.au.pv.sgsvr/en-gb/environment</u>.

This document is issued by the Company under its General Conditions of Service accessible at <u>www.sgs.com/en/Terms-and-Conditions.aspx</u>. Attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein.

Any holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client only. Any unauthorized alteration, forgery or falsification of the content or appearance of this document is unlawful and offenders may be prosecuted to the fullest extent of the law.

This report must not be reproduced, except in full.



APPENDIX D – PHOTOS





PHOTO 1: Overview of Site in North-eastern Direction



PHOTO 2: Overview of Site in in South-western Direction





PHOTO 3: Open Drain Along Northern Boundary



APPENDIX E - UNDERSTAND THE LIMITATIONS OF YOUR GEOTECHNICAL REPORT



UNDERSTAND THE LIMITATIONS OF YOUR GEOTECHNICAL REPORT

This report has been based on project details as provided to us at the time of the commission. It therefore applies only to the site investigated and to a specific set of project requirements as understood by ETS Geo Pty Ltd.

If there are changes to the project, you need to advise us in order that the effect of the changes on the report recommendations can be adequately assessed. ETS Geo Pty Ltd cannot take responsibility for problems that may occur due to project changes if they are not consulted.

It is important to remember that the subsurface conditions described in the report represent the state of the site at the time of investigation. Natural processes and the activities of man can result in changes to site conditions. For example, ground water levels can change or fill can be placed on a site after the investigation is completed. If there is a possibility that conditions may have changed with time, ETS Geo Pty Ltd should be consulted to assess the impact on the recommendations of the report.

The site investigation only identifies the actual subsurface conditions at the location and time when the samples were taken. Geologists and engineers then extrapolate between the investigation points to provide an assumed three-dimensional picture of the site conditions. The report is based on the assumption that the site conditions as identified at the investigation locations are representative of the actual conditions throughout an area. This may not be the case and actual conditions may differ from those inferred to exist. This will not be known until



construction has commenced. Your geotechnical report and the recommendations contained within it can therefore only be regarded as preliminary.

In the event that conditions encountered during construction are different to those described in the report, ETS Geo Pty Ltd should be consulted immediately. Nothing can be done to change the actual site conditions which exist but steps can be taken to reduce the impact of unexpected conditions. For this reason, the services of ETS Geo Pty Ltd should be retained through the development stage of a project.

Problems can occur when other design professionals misinterpret a report. To help avoid this, ETS Geo Pty Ltd should be retained for work with other design professionals to explain the implications of the report.

This report should be retained as a complete document and should not be copied in part, divided or altered in any way.

It is recommended that ETS Geo Pty Ltd is retained during the construction phase to confirm that conditions encountered are consistent with design assumptions. For example, this may involve assessment of bearing capacity for footings, stability of natural slopes or excavations or advice on temporary construction conditions.

This document has been produced to help all parties involve recognise their individual responsibilities.